

ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

Notice dated 10th March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 25th March 1929, for constructing Primary Boys' School at Tirthahalli, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Primary Boys' School at Tirthahalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing a Primary Boys' School at Tirthahalli, Shimoga District.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C.yd.	79
2	Filling jelly concrete for foundation	C.ft.	418
3	Size stone in clay, foundation and basement with bond stones	"	2,246
4	Burnt brick in clay (superstructure)	"	2,518
5	Burnt brick in chunam	"	541
6	Burnt brick in chunam for segmental arch work	"	112
7	Burnt stone slabs 6" thick dressed and fixed	S.ft.	165
8	Teakwood battened doors with shutters 1½" frame, etc., complete.	"	168
9	Teakwood windows, with battened shutters, frames, iron bars, etc.	"	119
10	Jungle wood (honne wood) wrought and put up with wood oiling and tarring wherever necessary.	C.ft.	157'04
11	Roofing with 1st Class Mangalore tiles on teak reepers ...	Sqr.	29'29
12	Ridge tiles set in mortar	R.ft.	134
13	Valleys with ½" teakwood planks, zinc sheets and chunam and cement gutters.	"	51
14	Chunam plastering	Sqr.	63'51
15	White washing as per plastering	"	6'46
16	Chacolate painting	"	13'13
17	Flooring with Mangalore tiles on 3" concrete bed and grouting with cement.	"	
18	Jungle wood eave board 10" wide with painting	R.ft.	232
19	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	Sqr.	3'97
20	Cement pointing to basement	"	3'26
21	Chunam border	Lump	sum
22	Clearing site and unforeseen charges	Lump	sum
23	For writing the name of the school in plastering, etc. ...	Lump	sum
24	Finials	No.	3
25	Cutting grooves in stone pillars	"	10
26	Perforated brick honey comb work	Lump	sum

Notice dated 12th March 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 25th March 1929, for constructing Town Hall at Sagara.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M. in office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of Rs. 700 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Town Hall at Sagar in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. A progress of not less than Rs. 3,000 per month is to be given this year.

10. Rates must be written in words and figures.

Abstract estimate of quantities for constructing a Town Hall at Sagar, Shimoga District.

No.	Items of works	Per	Quantity
1	Earthwork excavation, gravelly soil, foundation and filling in basement.	C.yd.	120
2	Filling in foundation, stone jelly concrete in mortar ...	C.ft.	962
3	Cut latrite stone in mortar, foundation, basement and super-structure.	"	9,180
4	Segmental arch work foundation, basement and superstructure.	"	231
5	Teakwood panelled doors with iron fittings ...	S.ft.	289'50
6	Teakwood windows with shutters only one side $\frac{1}{2}$ panelled at bottom, $\frac{1}{2}$ glazed at top with iron bars, etc., complete.	"	333'50
7	Circular pillar 15" dia. 11 $\frac{1}{2}$ ' high with base and capitals, etc. ...	No.	10
8	Teakwood wrought and put up including wood oiling ...	C.ft.	226'15
9	Iron trusses: ...	Cwt.	40
10	Rolled steel joists for varandah ...	"	8'2
11	Roofing with 1st Class Mangalore tiles with ceiling tiles on teak reepers, etc.	Sqr.	16'38
12	Roofing with pucca terrace 9" thick ...	"	10'64
13	Ornamental ridge tiles set in mortar ...	R.ft.	26
14	Plain ridge tiles set in mortar for hips ...	"	84
15	Plastering with chunam inside ...	Sqr.	55'52
16	White washing two coats ...	"	55'52
17	Pointing with chunam outside ...	"	33'35
18	Flooring with 1st Class Mangalore tiles on 3" concrete bed and cement pointing.	"	15'93
19	Flooring with Cuddapah slabs on 3" concret bed and cement pointing.	"	3'34
20	Silicate painting ...	"	14'12
21	Ornamental parapet wall ...	R.ft.	152
22	Cornice 9" thick ...	"	208
23	Ornamental pediment at centre in the front varandah including cornice, etc.	Lump	sum
24	Ornamental work over windows as per plan ...	No.	15
25	Vases over wall ...	"	5
26	Teakwood finials with flags ...	"	2
26A	Pediment over entrance and rooms ...	"	3
27	Jungle clearing, forming roads and sundry works ...	Lump	sum
28	Unforeseen works ...	"	"
28A	Armoured concrete or stone slabs for steps ...	S.ft.	75
29	Inscription stone, including laying foundation stone, etc.	Lump	sum